

Street Projects – MATA
P.O. Box 1845
Jonesboro, Arkansas 72403-1845
(870) 933-4616
(870) 933-4618 FAX



Engineering Department
P.O. Box 1845
Jonesboro, Arkansas 72403-1845
(870) 932-2438
(870) 933-4618 FAX

CITY OF JONESBORO

August 27, 2002

Ditch Clearing, Dredging, and Mowing or Shredding Specs.

1. It shall be the responsibility of the contractor to call one call 1-800-482-8998 for utility locates.
2. Cut (shred) trees from top of bank to top of bank 8 inches in diameter or smaller into mulch and leave no stump taller than 3 inches.
3. Trees over 8 inches in diameter to be looked at after ditch is mowed to determined what needs to be done. In no case shall a tree be left in the flow line of a ditch. Trees larger than 8 inches removed shall be placed on top of bank as directed be the City Engineer.
4. Mop out high spots as directed by the City Engineer.
5. When mopping out a ditch the maximum depth of water ponding shall be 4 inches deep in bottom of ditch at any point.

Equipment to be used at rate specified in contract.

1. Excavator 165 Horsepower, 34 foot reach with mower (shredder) attachment.
2. Excavator 150 Horsepower, 60 foot reach with 1 CY. Bucket.
3. Excavator 130 Horsepower, 35 foot reach with 1 1/4 C.Y. Bucket.
4. Excavator 150 Horsepower, 32 foot reach with 1 1/2 C.Y. Bucket.
5. Bulldozer 165 Horsepower, 13 foot wide blade.
6. Dragline, 50 foot Boom, 1 yard bucket

Company

Address

Representative

City/State

Title

Telephone No.

Signature

Date