



View Estimate

Print

PDF

Decline

Accept

Dennis Neal Resurfacing  
 Dennis Neal  
 411 Main Street  
 Swifton, AR 72471  
 Phone: 870-664-1224  
 Dennisneal52@gmail.com  
 dennisnealsrefinishing.com



City Of Jonesboro  
 330 S. Church  
 P.O. Box 1845  
 Jonesboro AR 72403-1845  
 Dkapales@jonesboro.org

## ESTIMATE

Estimate # 0000639

Estimate Date 07/05/2019

Item	Description	Unit Price	Quantity	Amount
	Pavilion 1 Restroom Women's: The floor area measures 26'8"X11'4". We will grind the floor to a 100 grit finish to remove existing coatings off of concrete to prep for refinishing. We will also prep the wall up from the floor level 8" to the first block line for refinishing adding a cove base to have a rounded transition from floor to wall. We will then resurface the floor and wall described above in a Multi-Stone epoxy resin finish.	3518.00	1.00	3,518.00
	Pavilion 1 Restroom Men's: The floor area measures 26'8"X11'4". We will grind the floor to a 100 grit finish to remove existing coatings off of concrete to prep for refinishing. We will also prep the wall up from the floor level 8" to the first block line for refinishing adding a cove base to have a rounded transition from floor to wall. We will also prep the area behind the toilets and urinals with a total linear footage being 62'9" and take that finish up the wall from the floor 4'. We will then resurface the floor and wall described above in a Multi-Stone epoxy resin finish.	5027.00	1.00	5,027.00
	Pavilion 3/4 Restroom Women's: The floor area measures 26'8"X11'4". We will grind the floor to a 100 grit finish to remove existing coatings off of concrete to prep for refinishing. We will also prep the wall up from the floor level 8" to the first block line for refinishing adding a cove base to have a rounded transition	3518.00	1.00	3,518.00

from floor to wall. We will then resurface the floor and wall described above in a Multi-Stone epoxy resin finish.

Pavilion 1 Restroom Men's:

4484.00 1.00 4,484.00

The floor area measures 26'8"X11'4". We will grind the floor to a 100 grit finish to remove existing coatings off of concrete to prep for refinishing. We will also prep the wall up from the floor level 8" to the first block line for refinishing adding a cove base to have a rounded transition from floor to wall. We will also prep the area behind the toilets and urinals with a total linear footage being 47'6" and take that finish up the wall from the floor 4'. We will then resurface the floor and wall described above in a Multi-Stone epoxy resin finish.

Campground Restroom Women's:

4979.00 1.00 4,979.00

The floor area measures 28'9"X11'5". We will grind the floor to a 100 grit finish to remove existing coatings off of concrete to prep for refinishing. We will also prep the wall up from the floor level 8" to the first block line for refinishing adding a cove base to have a rounded transition from floor to wall. We will also prep all of the shower walls up the wall from the floor level 6'8" up for refinishing. We will then resurface the floor and wall described above in a Multi-Stone epoxy resin finish.

Campground Restroom Men's:

5678.00 1.00 5,678.00

The floor area measures 28'9"X11'5". We will grind the floor to a 100 grit finish to remove existing coatings off of concrete to prep for refinishing. We will also prep the wall up from the floor level 8" to the first block line for refinishing adding a cove base to have a rounded transition from floor to wall. Their is a 22'3" linear footage behind the toilets and urinals that will go up the wall 4' from the floor level. We will also prep all of the shower walls up the wall from the floor level 6'8" up for refinishing. We will then resurface the floor and wall described above in a Multi-Stone epoxy resin finish.

Pavilion 5 Restroom Women's:

2847.00 1.00 2,847.00

The floor area measures 26'8"X11'4". We will repair any imperfections in the tile and grout lines to prep for refinishing as well as the tile that runs up the wall about 7" from the floor. We will then resurface the tile on floor and wall described above in a Multi-Stone epoxy resin finish.

Pavilion 5 Restroom Men's:

4360.00 1.00 4,360.00

The floor area measures 26'8"X11'4". We will repair any imperfections in the tile and grout lines to prep for refinishing as well as the tile that runs up the wall about 7" from the floor. We will also be prepping for refinishing 60 linear foot behind the toilets and urinals 4' up from the floor. We will then resurface the tile on floor and wall as well as the block area described above in a Multi-Stone epoxy resin finish.

Fort Rotary Restroom Women's:

1569.00 1.00 1,569.00

The floor area measures 14'8"X8'7". We will grind the floor to a 100 grit finish to remove existing coatings off of concrete to prep for refinishing. We will also prep the wall up from the floor level 8" to the first block line for refinishing adding a cove base to have a rounded transition from floor to wall. We will then resurface the floor and wall described above in a Multi-Stone epoxy resin finish.

Fort Rotary Restroom Men's:	2689.00	1.00	2,689.00
-----------------------------	---------	------	----------

The floor area measures 14'8"X8'7". We will grind the floor to a 100 grit finish to remove existing coatings off of concrete to prep for refinishing. We will also prep the wall up from the floor level 8" to the first block line for refinishing adding a cove base to have a rounded transition from floor to wall. There will also be 35 linear foot that will be refinished 4' up from the floor level behind the toilets and the urinal area. We will then resurface the floor and wall described above in a Multi-Stone epoxy resin finish.

<b>Subtotal</b>	38,669.00
<b>Total</b>	38,669.00
<b>Amount Paid</b>	0.00
<b>Estimate</b>	\$38,669.00