

MORTON DRIVE & MITCHELL DRIVE

Estimates for base preparation - set up base, 6" gravel base course, prime coat, hot mix asphalt. Estimates are based on current engineering cost factors, and on a 20' wide street in the above areas.

1393 cu. yds. gravel base
5911 sq. yds. set up
1773 gals. prime coat
650 tons hot mix asphalt

\$ 6,965.00

2,955.50

2,216.25

19,500.00

Total Project \$31,636.75

~~\$ 24,671.75~~

County
**100/house*

Due to escalation factors of oil prices, total may vary 5 to 10%.