



OVERALL FLOOR PLAN

1" = 20'-0"

6" CONCRETE FLOOR SLAB 4000PSI REINFORCE WITH #3 BARS @ 18" O.C. IN 1" ON 8" SOIL CEMENT 10% BY VOLUME BASE FLOOR TOLERANCE F1-35 / F1-25 APPLY LIQUID FLOOR DENSIFIER

UNDERHUNG CRANE SYSTEM FURNISHED AND INSTALLED BY TENANT. COLUMN BRACKETES FURNISHED BY BUILDING STEEL FABRICATOR TYPICAL

SAW CUT FLOOR SLAB CONTROL JOINTS TYP

FLOOR SLAB CONSTRUCTION JOINT OR CONTROL JOINT

COLUMN BLOCKOUT TYPICAL

1
A-4.2

1
A-4.2

1
A-4.0

1
A-4.1

1
A-4.1

4
A-4.3

1
A-4.0

No.	Date	Description
1	2/23/2016	ISSUE FOR REVIEW

NOTICE: This document discloses subject matter considered confidential by H+M Design Services, P.C. and on which H+M Design Services, P.C. has proprietary rights. Neither recipient nor possessor to reproduce the information or any part thereof, or to disclose and information related to same, or to use for any other purpose without the written permission of H+M Design Services, P.C.

HM
Design Services, P.C.
 50 Security Drive Jackson, Tennessee 38305
 Telephone: (731) 664-6300 Fax: (731) 664-6339

SCALE	As Indicated	PROJECT	NEW FACILITY FOR TIME SQUARE Jonesboro, AR	PROJECT NUMBER	15084
DRAWN	A/E	PM		SHEET NUMBER	A-1.1
Author	Checker	Approver		PLOT DATE	2/23/2016 3:23:13 PM
SHEET TITLE			FACILITY FLOOR PLAN		

PRELIMINARY NOT FOR CONSTRUCTION