

## Change Order

Proceed)

PROJECT (Name and address):	CHANGE ORDER NUMBER: 001	OWNER: 🛛
City of Jonesboro - New Facility for JETS	DATE: November 9, 2009	ARCHITECT:
TO CONTRACTOR (Name and address): Bailey Contractors, Inc. 101 CR 130 Jonesboro, AR 72401	ARCHITECT'S PROJECT NUMBER: 1-3628-08 CONTRACT DATE: November 15, 2009 CONTRACT FOR: General Construction	CONTRACTOR: ⊠ FIELD: □ OTHER: □
, , , , , , , , , , , , , , , , , , , ,	<b>OWS:</b> ed amount attributable to previously executed Construction	n Change Directives)
(Include, where applicable, any undispute See Attached list of Items	d amount attribulable to previously executed Construction	n Change Directives)
The original Contract Sum was		\$ 682,485
The net change by previously authorized	\$ 0.00	
The Contract Sum prior to this Change Or	\$ 682,485.00	
The Contract Sum will be decreased by this Change Order in the amount of		\$14,613
The new Contract Sum including this Cha	inge Order will be	\$ 667,872.00
The Contract Time will be increased by Z The date of Substantial Completion as of	ero (0) days. the date of this Change Order therefore is 200 days from d	late of contract (Notice to

NOTE: This Change Order does not include changes in the Contract Sum, Contract Time or Guaranteed Maximum Price which have been authorized by Construction Change Directive until the cost and time have been agreed upon by both the Owner and Contractor, in which case a Change Order is executed to supersede the Construction Change Directive.

## NOT VALID UNTIL SIGNED BY THE ARCHITECT, CONTRACTOR AND OWNER

Stuck Associates Architects	Bailey Contractors, Inc.
ARCHITECT (Firm name)	CONTRACTOR (Firm name)
(HAM)	101 CR 130 Bino
ADDRESS A T	ADDRESS /
	_ / Ci Bales
BY (Signature)	BY (Signature)
Paul Hoelscher	Kevin Bailey KrunBaile
(Typed name)	(Typed name)
	u117107
DATE	DATE .

1: OMIT FIRE SUPPRESSION SYSTEM. CHANGE CORRIDOR WALLS TO 1-HOUR PROVIDING 5/8" X-RATED GYPSUM BOARD ON EACH SIDE. EXTEND WALLS TO ROOI PROVIDE FIRE DAMPERS IN ANY DUCTS THAT PENETRATE CORRIDOR WALLS. CHANDOOR/FRAME RATING TO 45 MINUTE AND ADD CLOSERS AT ALL CORRIDOR DOORS RATED PROTECTION FOR ALL MEP DEVICES LOCATED IN THESE RATED WALLS. (THIS CONDITION APPLIES TO DISPATCH, WAITING AND RECEPTION — EXTEND RATED WAITHESE AREAS, EXCEPT FOR EXTERIOR WALLS.  DEDUCT	F AND SEAL. GE S. PROVIDE FIRE S SAME LLS AROUND \$16,154
2: PROVIDE 3 INCHES OF ASPHALT PAVING IN LIEU OF 4 INCHES SPECIFIED, A EXCEPT 'MAIN DRIVE'. THIS AREA TO REMAIN PAVING TYPE 1 AS SHOWN. CONCRET UNDER DRIVE THRU TO BE 4 INCHES.  DEDUCT	TE PAVING
4A: OMIT THE METAL ROOF PANELS, METAL DECK AND RIGID INSULATION SHO (EQUAL TO) STAR BUILDING SYSTEMS STARSHIELD ROOF PANEL IN 24 GAGE. NOT ENGINEERED BUILDING MUST BE DESIGNED SUCH THAT THE ROOF SYSTEM PROVIDE DIAPHRAGM. DEDUCT	DWN. PROVIDE E: PRE- ES REQUIRED \$20,052
7. OMIT PERIMETER BULKHEADS AROUND DRIVE THRU. PROVIDE METAL TRIM DEDUCT	·
9. PROVIDE STANDARD (WHITE) SURFACE-MOUNTED FANFOLD TOWEL DISPENS RECESSED TOWEL/TRASH DISPENSERS DEDUCT	
10A. OMIT UNIT HEATER SHOWN IN SPRINKLER RISER ROOM. DEDUCT	\$ 480
11. PROVIDE STANDARD GREY CONCRETE MASONRY UNITS IN LIEU OF COLORE SPECIFIED. DEDUCT	
12. PROVIDE ROOF PANELS IN GALVALUME FINISH IN LIEU OF PAINTED FINISH. DEDUCT	
13. CHANGE ROOF SLOPE TO 1:12. DEDUCT	\$ 232
14. PROVIDE STANDARD WALL SWITCHES IN LIEU OF OCCUPANCY DEDUCT	\$ 941
16. PROVIDE ROTARY CUT BIRCH DOORS IN LIEU OF RED OAK. DEDUCT	\$ 256
17. REDUCE THE FENCE ALLOWANCE TO \$25,000. DEDUCT	\$15,000
18. PROVIDE 2x4 CEILING GRID/TILE IN LIEU OF 2x2 SPECIFIED.	<b>\$</b> 377

	ADD RECIRCULATING PUMP LEAVE RETURN LINES TO FORM LOOP.	\$	245
20B.	ADD PIPING FOR RETURN SYSTEM.		
	PROVIDE PVC FOR ALL SEWER PIPING ABOVE SLAB. CT	\$ 1	,995
22. DEDU	PROVIDE KING-SIZE BRICK IN LIEU OF BRICK SPECIFIED. ADJUST COURSING AS F	≀EC .\$	NUIRED. 1,345
SPECIF	PROVIDE PRICING TO TAKE SITE WORK FROM EXISTING ELEVATION (APPX 12"-18 IED ELEVATION). PROVIDE SUITABLE BORROWED FILL FROM OFF-SITE LOCATION	I.	
	NUMBERING SHOWN IS FROM ORIGINAL VALUE ENGINEERING DOCUMENT. NOT	ALI	-

PROPOSED ITEMS WERE ACCEPTED.